


BRUHAT BANGALORE MAHANAGARA PALIKE**"SCHEDULE - B"****Name of Work: Filling of Pot Hole in Ward No.06, Byatarayanapura Sub Division.****Tender Number : INDENT 4500**

SNo	Item Name	Unit	Estimate Quantity	Approved Rates	
				In Figure	In Words
1	KSRRB M300-2: Making up loss of material / irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per specifications MORTH specification No. 3003,	Sqm	791.25	6.88	Rupees Six And Paise Eighty Eight Only
2	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification	cum	276.02	1081.00	Rupees One Thousand Eighty One Only
3	KSRRB 3000 Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2,	Sqm	1840.1	400.00	Rupees Four Hundred Only


Contractor
Executive Engineer
Byatarayanapura Division
Bruhat Bangalore Mahanagara Palike